


BOARD OF COMMISSIONERS

JANICE VAN NESS, CHAIR & CEO
Tuwanya C. Smith, Commissioner Post I
Dr. Doreen Williams, Commissioner Post II



DEPARTMENT OF FINANCE

SUE SANDERS, INTERIM CFO
TELEPHONE: 770-278-7555
FACSIMILE: 770- 278-8910

**Addendum No. 5
ITB No. 25-16
SPLOST 5C RESURFACING PROGRAM
July 9, 2025**

ITB #25-16 is hereby amended as follows:

- 1. A REVISED BID SCHEDULE IS ATTACHED TO THIS ADDENDUM AND MUST BE SUBMITTED WITH YOUR BID.**
- 2. Below are questions received and corresponding answers:**

A. Question: Per Addendum #2, the scope calls for all roads to be milled at 3.5", 2" 19mm, and 1.5" of 12.5mm. However, the bid schedule has OGI, 9.5 and milling at 1.5". Can we remove these items if they are not in the scope of work?

Answer: No, OGI is already included in the contract documents.

B. Question: Can you please add an item on the bid schedule for the 2" of 19mm?

Answer: Yes, please see attached Revised Bid Schedule.

C. Question: Based on the SY provided, I found these following quantities.

Milling @ 3.5" - 119,377 SY

19mm @ 2" - 11,938 Tons

12.5mm @ 1.5" - 9489 Tons

Can we adjust the bid schedule quantities to reflect the more accurate quantities expected?

Answer: No, ITB 25-16 is a unit price base bid. Unit prices will govern the project.

D. Question: Can we use LASA in lieu of Hydrated Lime per the attached GDOT bulletin?

Answer: Follow current GDOT standards.

E. Question: Can you provide more information on the Item "Excavation Rock" and where that could be used? Is that item part of the patching item to remove the existing material?


Answer: This will be addressed case by case. The following information will be incorporated into the Contract: *Rock Clause – If in the process of excavating for any work related to this Contract, the Contractor hits rock that is deemed by the Contractor to be above and beyond expected, Contractor shall stop work immediately and notify the Owner in*

BOARD OF COMMISSIONERS

JANICE VAN NESS, CHAIR & CEO

Tuwanya C. Smith, Commissioner Post I

Dr. Doreen Williams, Commissioner Post II



DEPARTMENT OF FINANCE

SUE SANDERS, INTERIM CFO

TELEPHONE: 770-278-7555

FACSIMILE: 770- 278-8910

writing. Work will proceed on an agreed hourly charged basis.

Contractor shall promptly, and before the conditions are disturbed, give a written notice to owners on encountering unforeseeable conditions adversely affecting the work. Owners shall investigate the site conditions promptly after receiving notice. If the conditions cause an increase in cost to contractor or the time required for performing any part of the work and were not reasonably foreseeable by an experienced contractor, an equitable adjustment shall be made under this clause and the contract modified in writing accordingly.

3. All other conditions remain in full force and effect.
4. If a bid has been submitted and anything in this Addendum causes the bidder to change the item offered or to increase or decrease the bid price, the new price and/or changes will be inserted below:

5. All bidders under this Invitation to Bid are kindly requested to acknowledge receipt of this Addendum on page BD.26 of the Bid Package.

Tina Malone

Tina Malone, CPPB CPPO

Procurement Manager

Department of Finance, Purchasing Division

ITB #25-16

SPLOST 5C RESURFACING PROGRAM

Contract Scope: 8.26 Miles of Roadway Resurfacing, including Milling, Patching, Asphalt Paving, and Striping on Numerous Roadway in Rockdale County.

Vendor: _____

Signature: _____

REVISED BID SCHEDULE OF ITEMS:

Line No.	Pay Item No.	Item	Unit	Approx Qty	Unit Price	Amount
5	150-1000	TRAFFIC CONTROL – (Incl Temporary Striping)	LS	1		
10	210-0200	GRADING, ADJUST SHOULDER TO GRADE - (2 Ft. Min Width, Incl Cutting Down High Shoulders, Grassing in Kind)	LM	7		
15	310-5060	GR AGGR BASE CRS, 6 INCH, INCL MATL (USED FOR PATCHING); Additional Quantities Included for Contingency Work.	SY	1,500		
20	402-3103	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE II, GP 2 ONLY, INCL BITUM MATL & H LIME (1.5 IN)	TN	6,620		
25	402-3130	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME (1.5 IN)	TN	6,520		
30	415-1010	ASPH CONC OPEN GRADED CRACK RELIEF INTERLAYER, GP 1 OR 2, INCL BITUM MATL & H LIME (2.0 IN)	TN	6,600		
35	413-0750	TACK COAT	GL	12,000		
40	432-0206	MILL ASPH CONC PVMPT, 1 1/2 IN DEPTH	SY	69,955		
45	432-0214	MILL ASPH CONC PVMPT, 3 1/2 IN DEPTH	SY	49,422		
50	647-6090	LOOP DETECTION 6' x 40' (CONTINGENCY ITEM)	EA	8		
55	653-0120	THERMOPLASTIC ARROW TP 2	EA	7		

Line No.	Pay Item No.	Item	Unit	Approx Qty	Unit Price	Amount
60	653-0130	THERMOPLASTIC PVMT MARKING, ARROW TP 3	EA	2		
65	653-0230	THERMOPLASTIC PVMT MARKING, WORD, TP 3A ("SCHOOL")	EA	3		
70	653-0231	THERMOPLASTIC PVMT MARKING, WORD, TP 4 ("AHEAD")	EA	3		
75	653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	400		
80	653-1804	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	LF	500		
85	653-1501	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, WHITE	LF	74,100		
90	653-1502	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, YELLOW	LF	82,800		
95	653-3501	THERMOPLASTIC SKIP TRAFFIC STRIPE, 5 IN, WHITE	GLF	300		
100	653-6004	THERMOPLASTIC TRAF STRIPING, WHITE	SY	200		
105	653-6006	THERMOPLASTIC TRAF STRIPING, YELLOW	SY	55		
110	654-1001	RAISED PAVEMENT MARKERS (TP 1, TP 2, TP 3)	EA	100		
115	999-0001	SPEED TABLE - COMPLETE	EA	1		
120	N/A	REMOVE/REPLACE CONC CURB & GUTTER (MATCH EXISTING IN KIND) (CONTINGENCY ITEM)	LF	100		
121	611-8050	MANHOLES TO GRADE	EA	1		
122	611-8140	ADJUST WATER VALVE BOX TO GRADE	EA	15		
123	205-0210	EXCAVATION ROCK	CY	100		
	402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME (2 IN)	TN	6520		
					TOTAL:	

Signature/Firm _____